

ITEM NO:	
PROJECT:	
DATE:	

Refrigerated Service Case



Lengths include end panels			
-5/8"H			

STANDARD FEATURES


- NOTE: Contact Factory for lead time
- NOTE: Glass warranty only applicable to first point of delivery
- Breeze~E (Type-II) w/ EnergyWise s/c refrigeration
- (1) Level of clear glass shelving removable and adjustable on 1" centers
- Blue Fin coated coil
- Compressor air intake from rear and out front panel at toe kick. Front panel cannot be blocked.
- Condensate pan (self-contained refrig. only)
- Integrated average product temperature of 40°F or less
- LED top & shelf lights
- One piece formed ABS plastic tub
- One year parts & labor; 5 year compressor warranty
 Vertical, fixed front & side UV bonded frameless glass

Features	Standard	Options
EXTERIOR COLOR	□ Black	□ Painted (non-stock colors, specify RAL#)
		□ Painted (stock colors, specify RAL#)
		□ Stainless steel
INTERIOR COLOR	□ Black	□ NOTE: Interior color must be FDA & NSF approved
		□ Painted (stock colors, specify RAL#)
		□ Stainless steel
PANEL EXTERIOR	□ Laminated (non-premium) Confirm	□ Laminated (premium) Confirm pattern/grain direction
	pattern/grain direction	□ Stainless steel
BASE SUPPORT	□ Adjustable, locking casters (n/a w/	□ 6"H stainless steel legs
	remote ref.)	□ Shims (standard w/ remote)
END PANEL LEFT	□ Full end panel	□ No end panel w/ synchronized defrost
END PANEL RIGHT	□ Full end panel	□ No end panel w/ synchronized defrost
LOWER FRONT PANEL	□ Black	□ Painted (stock colors, specify RAL#)
		□ Stainless steel
LOWER REAR PANEL	□ Black	□ Painted (stock colors, specify RAL#)
		□ Stainless steel
UPPER REAR	 Clear glass rear sliding doors 	□ Reflective glass rear sliding doors
LIGHTS	□ LED 3500K w/ frosted lens	□ LED 3000K w/ frosted lens
		□ LED 4000K w/ frosted lens
ELECTRICAL CONNECT	□ 6' straight blade power cord	□ 6' locking power cord (self-cont.)
	(self-cont.)	□ Electrical leads (remote)
REFRIGERATION	□ Breeze~E (Type-II) w/ EnergyWise	□ Breeze~E (Type-II) w/ EnergyWise s/c refrigeration
	s/c refrigeration (rear access)	(front access)
		□ NOTE: Remote only available w/base w/shims
		□ Remote w/thermostat, solenoid & TXV (front access)
		□ Remote w/thermostat, solenoid & TXV (rear access)
MISCELLANEOUS		□ 14.5" Base height extension
		□ Rear door lock
		□ Second year parts & labor warranty (excludes
		compressor)
ACCESSORIES		□ Clean Sweep® coil cleaner (n/a w/remote)

Option Notes: 1 - Cannot be combined w/ 6"H legs







NR7240RSV 30 5/8" 17 3/4" 7 3/4" NOTE: ALL DIMENSIONS APPROXIMATE

REAR VIEW "A" "B" NR3640RSV 12 5/8" 17 3/4" 7 3/4" NR4840RSV 18 5/8" 17 3/4" 7 3/4" NR6040RSV 30 5/8" 17 3/4" 7 3/4"

ELECTRICAL JUNCTION BOX (SUPPLIED WITH 6" LEADS OR POWER CORD) LOCATION OF DRAIN TUBE FOR REMOTE REF ONLY (SUPPLIED WITH 3/4" OR 11/2" PVC TUBE).

REFRIGERATION LINE CONNECTION.

REMOTE FLOOR SINK & UTILITIES ACCESS AREA.

SELF-CONTAINED CASE SERVICE ACCESS AREA.

DRY CASE SERVICE ACCESS AREA.

Model Technical Specifications																
Model	L"	L1"	L2"	System C	ircuit Volts		Phs	Freq	Amps	Watts	Wires	NEMA Plug	SST	Conv. Rack BTUH	Para. Rack BTUH	Est Wt
NR3640RSV	N/A	35.75	4.13	Remote(Type II)	Circuit #1	110-120	1	60	1.08	32	2+G	Leads Single	24.00	864	800	800
				Self-Contained	Circuit #1	110-120	1	60	9.76	762	2+G	5-15P or L5-15P	N/A	N/A	N/A	
NR4840RSV	N/A	47.75	4.13	Remote(Type II)	Circuit #1	110-120	1	60	1.08	35	2+G	Leads Single	24.00	1123	1040	850
				Self-Contained	Circuit #1	110-120	1	60	9.76	765	2+G	5-15P or L5-15P	N/A	N/A	N/A	
NR6040RSV N/A	59.75	4.13	Remote(Type II)	Circuit #1	110-120	1	60	1.38	52	2+G	Leads Single	20.00	1382	1280	1,050	
				Self-Contained	Circuit #1	110-120	1	60	10.06	782	2+G	5-15P or L5-15P	N/A	N/A	N/A	
NR7240RSV	N/A	71.75	4.13	Remote(Type II)	Circuit #1	110-120	1	60	1.38	55	2+G	Leads Single	20.00	1642	1520	1,150
				Self-Contained	Circuit #1	110-120	1	60	9.86	774	2+G	5-15P or L5-15P	N/A	N/A	N/A	

*** Does not include electric defrost on freezer models

Regu	latory	Approva	ls:

All Models Accordance with AHRI Std 1200 ETL Listed to UL 471

ETL Listed to CAN/CSA 22.2 No. 120

ETL Sanitation to NSF 7







Important Notes:

- 1) ELECTRICAL NOTE: If GFCI is required, a GFCI breaker MUST be used in lieu of a GFCI receptacle
- 2) Back side of counter must be open or vented the full length of the unit to allow proper ventilation for the refrigeration system.
- 3) Glass warranty only applicable to first point of delivery.

MARNING: This product can expose you to chemicals, including Urethane (Ethyl Carbamate), which are known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov.